

APPROVED SCHEDULE - B

Tender Notification EE/BTP/BBMP/E-PMT/07/2014-15, Date: 31.10.2014

Improvements to Roads, Drains and Covering Slab at Muneshwara Layout in Ward No. 10 (Doddabommasandra), Vidyanarayapura Sub Division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of	
				M LAKSHMINARAYANA	
				In Figures	In Words
1	273.6	Earth work excavation by manual means in Hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	111.0	Rupees One Hundred Eleven Only
2	45.6	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180 kgs with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregates @ 0.57 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	4847.0	Rupees Four Thousand Eight Hundred Forty Seven Only
3	729.6	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour etc complete as per specifications and directions of engineer in charge of the work	Sqm	292.0	Rupees Two Hundred Ninety Two Only
4	95.76	of design mix M20 with OPC cement @ 320 Kgs with 20mm and down size graded granite metal coarse aggregates @ 0.878cum and fine aggregates @ 0.459 cum with superplastisier @ 3lts confirming to IS 9103-1999 reaffirmed 2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining	Cum	6065.0	Rupees Six Thousand Sixty Five Only
5	57.46	Providing mild steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery etc complete as per specifications and directions of engineer in charge of the work	Qtl	7975.0	Rupees Seven Thousand Nine Hundred Seventy Five Only
6	273.6	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar(1:6) including fixing curing etc complete as per specifications and directions of engineer in charge of the work	Sqm	642.0	Rupees Six Hundred Forty Two Only
7	1521	Providing chamfering edges to stone slab 2.5cms. wide as per specifications. (only chamfered length shall be recorded) etc complete as per specifications and directions of engineer in charge of the work	Mtr	32.0	Rupees Thirty Two Only
8	273.6	Providing two line dressing to granite stone slab / granite stone masonry etc complete as per specifications and directions of engineer in charge of the work	Sqm	851.0	Rupees Eight Hundred Fifty One Only
9	259.92	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means including loading and unloading etc complete as per specifications and directions of engineer in charge of the work	Cum	73.0	Rupees Seventy Three Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92